Quality Clauses

Q-Code	QID	Title	Long-Text
QUALITY MANAGEMENT SYSTEMS			
QAQC02	1	QMS—QAQC02 QUALITY SYSTEM DESIGN	The Manufacturer's Quality System shall conform to the requirements described in SAE AS9100, Model for Quality Assurance in Design/Development, Production, Installation, and Servicing; and be approved in

QQD4K3	Q	QUALITY	PROGRAM

			*All definitions can be found at the following link under 'Counterfeit Work Definitions': http://www.lockheedmartin.com/us/suppliers/bu-info/space/space-tandc.html
APPROVAL / ACCEPTANCE			
QA1	Q	LOCKHEED MARTIN ACCEPTANCE AT DESTINATION	Articles ordered under this Contract are subject to final acceptance at the Lockheed Martin facility as set forth on the face of the Contract.
QA5B	Q	ACCEPTANCE TEST PROCEDURES	The Contractor shall prepare separate detailed test procedures, encompassing tests required for acceptance. Each item of hardware, or part thereof, which requires acceptance testing, shall be covered by an Acceptance Test Procedure. Acceptance Test Procedures require Lockheed Martin approval prior to the delivery of the first unit of hardware. Subsequent changes are subject to Lockheed Martin approval prior to incorporation. Where these tests are performed utilizing equipment controlled by computer

			- Serial and/or lot numbers of the hardware processed (if required) - Material process specification & revision number - Certification stating the special process was performed per the drawing/specification requirements - Processing Organization's name and address - Signature and date by a company official of the Processor attesting that the processes were performed to the required drawing/specification(s) and satisfy required acceptance criteria. For reference, Lockheed Martin defines a special Process as a method controlled by a contractually required specification where: 1. A product undergoes a physical, chemical or metallurgical transformation or inspection. Conformance to the specification cannot be readily verified by normal inspection methods, and 2. The quality of the product depends on use of specific equipment operated in a specific manner, under controlled conditions, by trained personnel with instructions, procedures or standards. Contractually required specifications are identified on the drawing or parts list for build-to-print items or identified within a designated section of the controlling specification for items being procured under the contract line item of this Purchase Order. Methods for obtaining EXOSTAR/P2P approval: Special Processor Approval by an on-site survey by Lockheed Martin or Lockheed Martin acceptance of third party accreditation. Accepted certifications include International Accreditation Forum (I.A.F.) certified bodies, Nadcap and A2LA. The Contractor performing special process work shall have an AS9003 Quality Management System as a minimum, current and approved by Lockheed Martin at the time of processing. AS9100 and ISO 9001 are an acceptable substitute for AS9003. These approvals must be current in P2P/EXOSTAR. Lockheed Martin approval of the Contractor's system to control its own special processors (P2P Approval Code: SQES00TQ99 or SQDANQ4M00). a. This approval is contingent upon the Contractor's procedural requirement for an on-site survey to an adequate process specific questionnaire and b. A vendor rating system that identifies unacceptable sub-tier performance with criteria for corrective action and criteria and frequency for re-survey and c. A list of special processor approval(s) that contains approval and expiration dates. Approvals must be current in P2P/EXOSTAR. Lockheed Martin approval of sub-tier contractor special processing does not relieve the Contractor of the responsibility to ensure that work performed by sub-tier contractors is in accordance with specification requirements.

Q1Z	Q	SUPPLIER NON-

must be included or referenced.

Repair: Used when the nonconforming article, material or service can be corrected to a usable condition, although its condition will not be identical with drawing / specification requirements. “The organization shall ensure that product which does not conform to product requirements is identified and controlled to prevent its unintended use or delivery.

The controls and related responsibilities for dealing with nonconforming product shall be defined in a documented procedure.

The organization’s documented procedure shall define the responsibility for review and authority for the disposition of nonconforming product and the process for approving personnel making these decisions.”

Data Requirements: Any nonconformance discovered by the organization, on products in their control, shall be documented by the organizations’ approved method of nonconformance reporting. This shall include a detailed description of the nonconformance; location (by drawing reference point, hardware reference point, clock location, etc.); and exact callout of the violation by drawing or specification requirement (including, sub-paragraph or illustration number). It shall also list what type of inspection revealed the discrepant condition, and what, if any, subsequent actions were taken prior to disclosure. Dimensional violations shall include “should be” and “is” dimensions, and tool(s) calibration traceability numbers.

Nonconformance Preliminary Review: The preliminary review process shall be initiated with the identification and documentation of a nonconformance. A preliminary review shall be the initial step performed by the organization to determine if the nonconformance needs to be reported to the customer (see below), and to determine if the nonconformance is minor and can be re-worked to a condition that completely conforms to the drawing or specification requirements.

Note: preliminary review does not negate the requirement to identify, segregate, document, report and disposition nonconformances.

Nonconformances shall be reported to the customer under the following conditions. When notification is required, notification shall be within 3 working days after the nonconformance is discovered.

· The problem is detected during one of the following:
1. C0 (ed)3.onfalon, oaifiope (n)1.70 (c)-6.90 (e)5 (,)3.70 (d)1.80 (r)-3.30 ( )1.80 (th)-9.30q(ed)3.20 u-7.80 (l)5 ( )1

· And it is:

1. Flight hardware
2. Flight Hardware Spares
3. Equipment that is representative of flight hardware (flight-like hardware), including prototype and qualification hardware

specification and resubmitted to Buyer. When an LM Discrepancy Report (DR) or Nonconformance Report (NCR) IS FORWARDED TO Supplier with rejected items, the DR or NCR number shall be entered on Supplier's shipping document. Supplier's shipping documentation shall include : (i) a statement detailing the corrective action taken to prevent recurrence of the cause of rejection or recommended action to avoid further rejection if cause of rejection is beyond Supplier's control; and (ii) a statement indicating whether the item was reworked or replaced. If reworked, a description of the rework operations performed shall be

			· Reference to previous NDI/NDT reports for repair/rework if applicable; · Reference to attached recordings i.e., films or photographs if applicable; A record of the procedures or techniques used and actual results shall remain on file for at least five years after shipment to Customer and shall be furnished to Customer upon request. These records shall include all information required in the previous paragraph as well as acceptance / rejection criteria, and related test instrument data used in the NDI/NDT process.
QB2A	Q	RAW CASTINGS AND FORGINGS	Two samples of all raw castings and forgings are required from new or reworked dies or molds and must be approved by Lockheed Martin prior to run of production parts. Unless Lockheed Martin source surveillance is a requirement of the Contract, the samples shall be forwarded to Lockheed Martin Receiving Inspection with the actual results of layout inspection, radiographs, and actual chemical and physical test results. When Lockheed Martin source surveillance is a requirement of the Contract, the layout and test data shall be evaluated at the Contractor's facility. In either case, first article approval by Lockheed Martin is required prior to the start of production. The Contractor is responsible for obtaining Lockheed Martin approval of any change in processes or tooling using the same approval instructions stated above.
QB3B	Q	TENSILE TEST SAMPLES	Two (2) separately cast test bars, coupons, or appendages as defined by the applicable specification or drawing shall be submitted with each lot delivered.
QB6	Q	NEUTRON RADIOGRAPHIC INSPECTION FOR COMPONENTS	Components ordered require neutron radiographic inspection in accordance with LAC SPEC-3701.An original neutron radiograph must be submitted to LM for review and approval at the time of hardware delivery.
QB9	Q	TEST SAMPLES	

			package, mark, and label, in accordance with Department of Transportation Hazardous Materials Regulations and competent authority shall be included in the shipment. Articles defined in this Purchase Agreement are subject to Lockheed Martin inspection at destination and may not be accepted by Lockheed Martin if the contractor fails to ship the above data. Upon receipt at Lockheed Martin, the data will be sent to the LM Ordnance Storage facility operator.
QQK	Q	ABBREVIATED RAW MATERIAL CERT	Hardware delivered per this order shall be traceable to the raw material used for manufacture by source (lot, batch or heat number, material type, specification, applicable revision letter or number and records of acceptance).The lot identifier shall be recorded on all certificates and packages for this order.
QSN	Q	Data required with shipment	Drawings, sketches, and specifications sufficient to inspect and/or test this material shall accompany each shipment under this contract.
QTD1	Q	DATA LIST NOT A REQUIREMENT	Design documentation as specified by this procurement document may contain a reference note to the Data List. The Data List has been discontinued as part of the design documentation package for this item.
QTM6	Q	MFG'D ARTICLES RAW MAT'L TEST REPORTS	Supplier (or manufacturer) shall maintain on file, and Supplier shall assure availability for Buyer's review upon request, results of chemical and/or physical tests required to satisfy specification requirements for raw materials used in the manufacture of items delivered under this order. Unless otherwise specified, files of such test results shall be retained for a minimum of three (3) years after completion of Supplier's performance under this order.
DIMENSIONAL INSPECTION			
Q56	Q	DIMENSIONAL INSPECTION 100%	Supplier shall perform 100% detailed/dimensional inspection, record the actual dimensional data for all drawing characteristics, and compliance with drawing notes for all parts. The recorded data, related material, and process certs (as applicable) shall be delivered with the parts for each lot shipped.
QAQC17	Q	AQC17 100% ATTRIBUTE CLAUSE	"The organization shall submit (1) reproducible copy of all inspection documentation stamped or signed by the responsible quality inspector showing 100% inspection for all attributes noted on the drawings, for all parts submitted under this Contract/Purchase Order."
QD36	Q	CRITICAL CHARACTERISTIC INSPECTION REQUIREMENTS	The contractor shall perform 100% inspection of critical characteristics identified in the Lockheed Martin engineering document. The contractor shall submit a certificate of compliance with each shipment attesting that all critical characteristics have been verified, to meet the requirements of the engineering document(s). The certification shall contain as a minimum - A listing of the critical characteristics verified, - The name of contractor, - Part number, - Purchase order number, - Serial number(s) (when applicable) - Quantity of parts shipped. Certification must be validated by an authorized representative of the contractor's Quality Department, by either an Inspection Stamp or signature and a date in which the inspection occurred.
QEH	Q	DIMENSIONAL INSPECTION CRITICAL CHARACTERISTICS	The contractor shall perform 100% inspection of critical characteristics identified in the Lockheed Martin engineering document. The contractor shall submit a certificate of compliance with each shipment attesting that all critical characteristics have been verified, to meet the requirements of the engineering document(s). The certification shall contain as a minimum a listing of the critical characteristics verified, the name of contractor, part number, purchase order number, serial number(s) (when applicable) and quantity of parts

			shipped. Certification must be validated by an authorized representative of the contractor's Quality Department, by either an Inspection Stamp or signature and a date in which the inspection occurred.
QQB	Q	DIMENSIONAL INSPECTION REPORT	

			packaging is in accordance with the drawing, appropriate ASTM, MIL, or other applicable customer specified requirement.
QAQC21	Q	AQC21 PACKAGING, HANDLING AND LABELING	The organization shall provide packaging that maintains the quality of the fabricated item and prevents damage, deterioration, substitution or loss in transit. The organization shall label the exterior of the package to ensure adequate identification of precautions needed to ensure the integrity of the product being shipped. The organization must specify the handling and shipping methods that ensure proper and on-time delivery without damage to the product. The organization shall ensure that special labeling requirements shall also be listed in the appropriate shipping documents and on each package.
QAQC29	Q	AQC29 ESD PROTECTION PROGRAM AND PACKAGING	The organization shall document and implement an ESD Control Program in accordance with ANSI/ESD

QZ281	Q	D941159	D941159, Memo of Agreement Btwn LMSC and Ford Aerospace Communication Corp. Pertaining to Procurement Rqmts for LMSC D915710A STPM Rqmts
QZ282	Q	D941160	D941160, Memo of Agreement Btwn LMSC and ITT Cannon electric Co., Pertaining to Acceptance Testing of A3TK Umbilical Plug Refurbishment
QZ283	Q	D941161	D941161, Memo of Agreement Btwn LMSC/MSD and Kaman Instrumentation Corp.
QZ284	Q	D941164	D941164, Memo of Understanding D5 Supplier Direct Ship Hardware List
QZ285	Q	D941165	D941165, Direct Ship of Missile Hardware to SWFLANT Plan
QZ286	Q	D988446CB AD	D988446BC, Addendum (Exceptions) to LMSC/D824156C Applicable to Contracts Btwn LMSC MSD & Genicom Corp., Pertaining to STPM Rqmts for Trident II (D5) Relays
QZ287	Q	D990249B	D990249B, Memo of Understanding Btwn LMSC and ARC Pertaining to Procurement Rqmts for D5 Nose Fairing Jettison Motor PBCS Gas Generator
QZ30	Q	F120040	F120040, Letter of Agreement Btwn LMSC & D5 Multilayer Board Suppliers Pertaining to STPM Rqmts for Missile System Hardware
QZ300	Q	D824158-15	D824158-15, DRD - FTS Filter Crystal Assembly
QZ302	Q	SMP010787U06	SMP010787U06, LOA between LM and IRC (Division of TRW) pertaining to STPM D824156 and STPM SMP010760U05
QZ303	Q	SMP010707U05	SMP010707U05, PAQR for G&H PMM Connectors (changes from D915703-1, Rev C)
QZ305	Q	SMP010704U05A	SMP010704U05A, Product Assurance Quality Requirements for Nose Cap and Nose Fairing Manufacture – Updated.
QZ306	Q	SMP010761U05	SMP010761U05, Product Assurance Quality Requirements for Electrical, Electronic and Electro-Mechanical (EEE) Devices – Updated
QZ307	Q	SMP010782U05-24	SMP010782U05-24, Detail Requirements Document for Inductors and Transformers for Teident II (D5) Program – Updated
QZ308	Q	SMP010782U05-21	SMP010782U05-21, Detail Requirements Document for Resistors for Trident II (D5) Program - Updated
QZ309	Q	SMP010782U05-19	SMP010782U05-19, Detail Requirements Document (DRD) for Relays Trident II (D5) Program - Updated
QZ31	Q	F120054	F120054, PAWS 49 - Using Supplier Use and Control of Pre-Released Hardware
QZ310	Q	SMP010789U06	SMP010789U06 MOU between LMSSC & OECO pertaining to STPM SMP010782U05-24
QZ311	Q	SMP010790U06	SMP010790U06 MOU between LMSSC & OECO pertaining to PAQR SMP010761U05 & DRD SMP010782U05-24
QZ316	Q	SMP010783U05A	SMP010783U05A – Memorandum of Understanding between LMSSC-MSO and Hamilton Sundstrand Aerospace applies.
QZ317	Q	SMP010708U07	SMP010708U07 – Letter of Agreement pertaining to Supplier Technical Program Management requirements (STPM) D915720, between Lockheed Martin Space AND Paine Electronics LLC (Paine).
QZ318	Q	SMP010713U08	

QZ33	Q	F120056	F120056, PAWS 94 - Advanced Procurement Program LMSC Product Assurance Source Surveillance
QZ34	Q	F120058	F120058, PAWS 42 - Functional Test Requirements for Support Equipment (SE) Spare Parts
QZ35	Q	F120060	F120060, PA Quality Rqmts for Reliability Test Data Failure Data Corrective Action Reporting
QZ37	Q	F120062	F120062, PAWS 8 - Reliability Test Data- Failure Data and Corrective Action Reporting
QZ38	Q	F120063	F120063, PAWS 35 - Product Assurance Requirements for Original Weld/Braze Provisions and Revisions
QZ39	Q	F120064	F120064, PAWS 44 - Product Assurance Requirements for "Services" Subcontracts for Maintenance of LMSC Government Funded or Furnished Test Equipment

QZ64	Q	F120168	F120168, Addendum (Exceptions) to LMSC/D824156C Applicable to Contracts Btwn LMSC MSD & Leach Corp for Trident II (D5) Relays
QZ65	Q	F120169	F120169, Addendum (Exceptions) to LMSC/D824156C Applicable to Contracts Btwn LMSC & Hadley Co. Pertaining to STPM Rqmts for Trident II (D5) Transformers & Inductors
QZ66	Q	F120171	F120171, Letter of Agreement Btwn LMSC & SPL Pertaining to MSD PA Review & Approval of Blanket Purchase Agreements for the Consignment of Spares & Consoles to LMSC Suppliers
QZ69	Q	F120186	F120186, Storage & Surveillance Plan for PBCS Gas Generator Materials and Nose Fairing Jettison Motor (NFJM) Material. Supplier Location: Aerojet-General Corporation
QZ72	Q	F120192	F120192, LOA Between LMSSC and Aerojet Pertaining to Qualification Verification (STPM) for Post Boost Control Generators
QZ73	Q	F120193	F120193, Addendum (Exceptions) to LMSC/D824156C applicable to Contracts Btwn LMSC MSD & Mawell Sierra Labs Pertaining to STPM Rqmts for Trident II (D5) Low Pass Filters
QZ76	Q	F120199	F120199, Addendum (Exceptions) to LMSC/D824156C applicable to Contracts Btwn LMSC MSD & Angstrohmn Precision, Inc., Pertaining to STPM Rqmts for Trident II (D5) Resistors
QZ77	Q	F120200	F120200, PA Quality Rqmts (PAQR) for Linear, Single-Axis Accelerometers
QZ78	Q	F120201	F120201, LOA - LMSSC & ATI Wah Chang pertaining to procurement requirements for D5 PBCS Manifold
QZ79	Q	F120204	F120204, Letter of Agreement Btwn LMSC & Moog, Inc., Seneca & Jamieson Rds., Pertaining to Quality Verification (STPM) Rqmts for Servoactuator Assemblies
QZ80	Q	F120215	F120215, Memo of Understanding Btwn LMSC & Loral Aeronutronic Pertaining to Procurement Rqmts for Loral Aeronutronic Integrated Valve Assem. and Sequencer Valve Assem.
QZ81	Q	F120218	F120218, Storage & Surveillance Plan for TVC Gas Generator Materials. Supplier Location: ATK Alliant Systems Co. LLC
QZ82	Q	F120219	F120219, Storage & Surveillance Plan for Propellant. Supplier Location: Crane Division (Naval Surface Warfare Center)
QZ83	Q	F120220	F120220, Storage & Surveillance Plan for Coils. Supplier Location: Tyco Electronics Corporation
QZ84	Q	F120221	F120221, STPM requirements for Reentry Body Inertial Measurement Unit (RIMU)
QZ85	Q	F120223	F120223, Addendum (exceptions) to LMSC/D824156 applicable to contracts between LMSC and Dale Electronics, Inc., Columbus, NE
QZ86	Q	F120224	F120224, Addendum (exceptions) to LMSC/D824125 applicable to contracts between LMSC and Croven Crystals, LTD
QZ87	Q	F120233	F120233, LOA between LMSC and Sundstrand Aerospace Rockford for first and second stage gas hydraulic assemblies
QZ88	Q	F120234	F120234, Storage & Surveillance Plan for Connector Castings. Supplier Location: Smith Tubular Systems
QZ90	Q	F120246	F120246, Storage & Surveillance Plan for Tubes. Supplier Location: Ensign Bickford
QZ91	Q	F120247	F120247, Storage & Surveillance Plan for Op Amp Chip. Supplier Location: Paine Corporation
QZ92	Q	F120248	F120248, LOA between LMSC and Honeywell AlliedSignal Inc., Aerospace Systems and Equipment for Third Stage Hydraulic Assemblies
QZ93	Q	F120250	F120250, LOA between LMSC and AlliedSignal Aerospace, Redmond WA
QZ94	Q	F120252	F120252, PAWS 101, Requalification Considerations for Trident II Program
QZ95	Q	F120262	F120262, Memo of Understanding, Sunstrand Rockford and LMMS Inspection Requirements Sunstrand Machine Facilities

Updated: QZ92	Per FBM Request

3/8/2011	Edited: QZ204, QZ238, QZ241, QZ253, QZ257, QZ263, QZ271	Minor FBM Code edits
3/9/2011	Removed: QZ184, QZ190, QZ195	Codes Deactivated
5/3/2011	Removed: QZ44, QZ45, QZ46, QZ57,	

11/17/2015	Removed: Q19B, Q37, Q57, QA2C, QA4H, QAQC05, QAQC07, QAQC10, QAQC12, QAQC18, QAQC19, QAQC30, QAQC31, QB12, QCC, QD13, QD15, QD16, QD5, QD8, QGL, QLT, QP3, QQD4K7, QQMY, QQS5, QQS5C, QQT8, QQTC5, QS11, QS5B, QS7, QT4C, QT4F, QTB9, QTC1, QTC3, QTR	Codes Deactivated
	Edited: QAQC13	Updated text to align with the language required by the Acquisition Compliance matrix
9/26/2016	Removed: QTU	Code Deactivated
	Added: QDTS	Dock To Stock Process
	Added: QB14	Supplier Data Sheet Submittal
	Added: QQBR	Reduced Dimensional Inspection Report
	Updated: QCF	Updated text to include physical and electronic signature
	Updated: QAQC08 Updated: QD27	Updated text of where contractually required specifications are identified